


(NOT ALL SYMBOLS & ABBREVIATIONS ARE NECESSARILY USED ON THIS PROJECT)


	DRAIN
	P-TRAP
	BALL VALVE
	CHECK VALVE
	MIXING VALVE
	RELIEF VALVE
	GLOBE VALVE
	GATE VALVE
	UNION
	VACUUM BREAKER
	SHOCK ABSORBER
	CONNECT TO EXISTING
	DISCONNECT FROM EXISTING

DRAWING NO.	DRAWING TITLE
P-001	PLUMBING PLAN, SYMBOLS, NOTES, DETAILS, SCHEDULES & DRAWING LIST
P-100	PLUMBING SPECIFICATIONS


DESIGNATION	FIXTURE	SERVICE CONNECTION							REMARKS
		S	W	IV	V	CW	HW	G	
EW	EYE WASH	-	1¼"	-	1½"	-	½"	-	GUARDIAN MODEL G1814. MOUNT AT RIM HEIGHT OF 33".
SS	SERVICE SINK	-	2"	-	1½"	½"	½"	-	COLUMBIA PRODUCTS MODEL 5A2F SINK WASH STATION (COMES WITH 2 FAUCETS MOUNT AT RIM HEIGHT OF 35".
SI	SEDIMENT INTERCEPTOR	-	2"	-	-	-	-	-	ZURN MODEL Z1180
MV	MIXING VALVE	-	-	-	-	½"	½"	-	GUARDIAN G3600LF THERMOSTATIC MIXING VALVE




4 KEY PLAN  
SCALE: NTS



1A PLUMBING DEMOLITION DETAIL  
SCALE: 1/2" = 1'-0"



1B PLUMBING CONSTRUCTION DETAIL  
SCALE: 1/2" = 1'-0"



2 PLUMBING CONSTRUCTION DETAIL  
SCALE: 1/2" = 1'-0"

## GENERAL NOTES

1. ALL WORK SHALL CONFORM TO THE REQUIREMENTS OF THE NEW YORK STATE BUILDING CODE, UTILITY COMPANY REQUIREMENTS, AND THE BEST TRADE PRACTICES.
2. BEFORE COMMENCING WORK, THE CONTRACTOR SHALL FILE ALL REQUIRED INSURANCE CERTIFICATES WITH THE DEPARTMENT OF BUILDINGS, OBTAIN ALL REQUIRED PERMITS, AND PAY ALL FEES REQUIRED BY THE GOVERNING NEW YORK STATE AGENCIES.
3. THE DRAWINGS SHOW THE GENERAL ARRANGEMENT OF ALL PIPING AND EQUIPMENT AND INDICATE THE REQUIRED SIZE AND POINTS OF TERMINATION OF THE PIPING AND SUGGEST PROPER ROUTING OF SAME. HOWEVER, IT IS NOT THE INTENTION OF THE DRAWINGS TO SHOW ALL NECESSARY OFFSETS, OBSTRUCTIONS OR STRUCTURAL CONDITIONS. IT SHALL BE THE RESPONSIBILITY OF THIS CONTRACTOR TO INSTALL HIS WORK IN SUCH A MANNER THAT IT WILL CONFORM TO THE STRUCTURE, AVOID OBSTRUCTIONS, PRESERVE HEADROOM AND KEEP OPENINGS AND PASSAGEWAYS CLEAR WITHOUT FURTHER CONSTRUCTION OR COST.
4. INSTALL WORK SO AS TO BE READILY ACCESSIBLE FOR OPERATING, MAINTENANCE AND REPAIR. MINOR DEVIATIONS FROM DRAWINGS MAY BE MADE TO ACCOMPLISH THIS, BUT CHANGES OF MAGNITUDE WHICH INVOLVE EXTRA COST SHALL NOT BE MADE WITHOUT APPROVAL.
5. THE CONTRACTOR SHALL COORDINATE ALL WORK PROCEDURES WITH THE STIPULATIONS OF LOCAL AUTHORITIES, BUILDING MANAGEMENT OR BOARD OF DIRECTORS.
6. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROTECTION OF ALL CONDITIONS AND MATERIALS WITHIN THE PROPOSED CONSTRUCTION AREA. THE CONTRACTOR SHALL DESIGN AND INSTALL ADEQUATE SHORING AND BRACING FOR ALL STRUCTURAL REMOVALS. THE CONTRACTOR SHALL HAVE SOLE RESPONSIBILITY FOR ANY DAMAGE OR INJURIES CAUSED BY OR DURING THE EXECUTION OF THE WORK.
7. THE CONTRACTOR SHALL LAY OUT HIS OWN WORK, AND SHALL PROVIDE ALL DIMENSIONS REQUIRED FOR OTHER TRADES.
8. ALL WORK SHALL BE PERFORMED BY PERSONS LICENSED IN THEIR TRADES, WHO SHALL ARRANGE FOR AND OBTAIN THROUGH THE DEPARTMENT OF BUILDINGS ALL REQUIRED PERMITS, INSPECTIONS AND REQUIRED SIGN OFFS.
9. THE CONTRACTOR SHALL DO ALL CUTTING, PATCHING, REPAIRING AS REQUIRED TO PERFORM ALL OF THE WORK INDICATED ON THE DRAWINGS, AND ALL OTHER WORK THAT MAY BE REQUIRED TO COMPLETE THE JOB.

[illegible]

2 Holland Avenue  
White Plains, NY 10603  
(914) 332-7658

WARNING: IT IS A VIOLATION OF THE NYS  
EDUCATION LAW ARTICLE 145 FOR ANY PERSON,  
UNLESS HE IS ACTING UNDER THE DIRECTION OF  
A LICENSED PROFESSIONAL ENGINEER, TO ALTER  
THIS ITEM IN ANY WAY.

Client or Agent

**SUNY PURCHASE  
COLLEGE**

New York, NY

Project Title	PAINT DECK ADA SINK
---------------	---------------------

Drawing Title
PLUMBING PLAN, SYMBOLS, NOTES, DETAILS, SCHEDULES & DRAWINGS LIST

Scale	AS NOTED	Drawing No. <b>P-001</b>
Date	5/18/22	

Drawn PA	C.E. Job No. 24045
Checked MQ	Copyright©2016 by Collado Engineering, P.C.

