

**AIR CONDITIONING VRF INDOOR FAN COIL UNIT SCHEDULE**

UNIT NO.	AREA SERVED	NOMINAL HEATING CAPACITY (BTU/h)	NOMINAL COOLING CAPACITY (BTU/h)	CFM	OUTSIDE AIR	ESP (IN WC)	COOLING DATA				HEATING DATA				ELECTRICAL DATA				REMARKS			
							TOTAL CAPACITY (BTU/h)	SENSIBLE CAPACITY (BTU/h)	EAT (°F)	EB (°F)	LAT (°F)	TOTAL CAPACITY (BTU/h)	ENGINEERING AIR TEMP.	LEADING AIR TEMP.	FAN QTY.	MCA	MFS	VOLTAG		WEIGHT LBS	MODEL	
SYSTEM AC-1A	DIMMER RM A	72,000.0	80,000.0	2542	95	0.60	65,561.1	65,561.1	75.0	59.0	50.9	51.4	15.2	70	88.7	2	7.7	15	208	214	PFT-P72MMSU-E	1.2,3,4,5,6
SYSTEM AC-2A	DIMMER RM A	72,000.0	80,000.0	2542	95	0.60	65,561.1	65,561.1	75.0	59.0	50.9	51.4	15.2	70	88.7	2	7.7	15	208	214	PFT-P72MMSU-E	1.2,3,4,5,6
SYSTEM AC-1B	DIMMER RM B	30,000.0	34,000.0	918	95	0.60	27,140.7	25,694.9	75.0	59.0	48.8	21,621.9	70	91.8	2	0.63(208V)	0.63(230V)/15	208	46	46	PFT-P30MKMU-E2	1.2,3,4,5
SYSTEM AC-2B	DIMMER RM B	30,000.0	34,000.0	918	95	0.60	27,140.7	25,694.9	75.0	59.0	48.8	21,621.9	70	91.8	2	0.63(208V)	0.63(230V)/15	208	46	46	PFT-P30MKMU-E2	1.2,3,4,5
SYSTEM AC-3B	DIMMER RM B	30,000.0	34,000.0	918	95	0.60	27,140.7	25,694.9	75.0	59.0	48.8	21,621.9	70	91.8	2	0.63(208V)	0.63(230V)/15	208	46	46	PFT-P30MKMU-E2	1.2,3,4,5
SYSTEM AC-4B	DIMMER RM B	30,000.0	34,000.0	918	95	0.60	27,140.7	25,694.9	75.0	59.0	48.8	21,621.9	70	91.8	2	0.63(208V)	0.63(230V)/15	208	46	46	PFT-P30MKMU-E2	1.2,3,4,5
SYSTEM AC-1C	DIMMER RM C	30,000.0	34,000.0	918	95	0.60	27,140.7	25,694.9	75.0	59.0	48.8	21,621.9	70	91.8	2	0.63(208V)	0.63(230V)/15	208	46	46	PFT-P30MKMU-E2	1.2,3,4,5
SYSTEM AC-2C	DIMMER RM C	30,000.0	34,000.0	918	95	0.60	27,140.7	25,694.9	75.0	59.0	48.8	21,621.9	70	91.8	2	0.63(208V)	0.63(230V)/15	208	46	46	PFT-P30MKMU-E2	1.2,3,4,5
SYSTEM AC-3C	DIMMER RM C	30,000.0	34,000.0	918	95	0.60	27,140.7	25,694.9	75.0	59.0	48.8	21,621.9	70	91.8	2	0.63(208V)	0.63(230V)/15	208	46	46	PFT-P30MKMU-E2	1.2,3,4,5
SYSTEM AC-4C	DIMMER RM C	30,000.0	34,000.0	918	95	0.60	27,140.7	25,694.9	75.0	59.0	48.8	21,621.9	70	91.8	2	0.63(208V)	0.63(230V)/15	208	46	46	PFT-P30MKMU-E2	1.2,3,4,5
SYSTEM AC-1D	DIMMER RM D	30,000.0	34,000.0	918	95	0.60	27,140.7	25,694.9	75.0	59.0	48.8	21,621.9	70	91.8	2	0.63(208V)	0.63(230V)/15	208	46	46	PFT-P30MKMU-E2	1.2,3,4,5
SYSTEM AC-2D	DIMMER RM D	30,000.0	34,000.0	918	95	0.60	27,140.7	25,694.9	75.0	59.0	48.8	21,621.9	70	91.8	2	0.63(208V)	0.63(230V)/15	208	46	46	PFT-P30MKMU-E2	1.2,3,4,5
SYSTEM AC-3D	DIMMER RM D	30,000.0	34,000.0	918	95	0.60	27,140.7	25,694.9	75.0	59.0	48.8	21,621.9	70	91.8	2	0.63(208V)	0.63(230V)/15	208	46	46	PFT-P30MKMU-E2	1.2,3,4,5
SYSTEM AC-4D	DIMMER RM D	30,000.0	34,000.0	918	95	0.60	27,140.7	25,694.9	75.0	59.0	48.8	21,621.9	70	91.8	2	0.63(208V)	0.63(230V)/15	208	46	46	PFT-P30MKMU-E2	1.2,3,4,5

**(BASED ON MITSUBISHI OR ENGINEER APPROVED EQUAL)**

**NOTES:**

1. NOMINAL HEATING CAPACITIES ARE BASED ON INDOOR COIL EAT OF 80/67°F (DB/MB), OUT DOOR OF 95°F (DB)
2. NOMINAL HEATING CAPACITIES ARE BASED ON INDOOR COIL EAT OF 70°F (DB), OUTDOOR OF 43°F (DB)
3. SET OUTDOOR UNIT SCHEDULE FOR OUTDOOR AMBIENT CONDITIONS, CONNECTED CAPACITY, AND OTHER FACTORS ASSOCIATED WITH OUTDOOR UNIT SCHEDULE.
4. CORRECTED CAPACITIES/CONTROL DIAGRAM FOR INDICATION OF REQUIRED INDOOR UNIT REMOTE CONTROLLERS, SYSTEM CONTROLLERS, AND INTERGRATION DEVICES.
5. SETTING (FULL DEMAND) COOLING.
6. FURNISH WITH DRAIN PAN LEVEL SWITCH ACCESSORY, MODEL PHS-1

**MITSUBISHI CITY MULTI VFR OUTDOOR UNIT SCHEDULE**

UNIT	TAG REFERENCE	LOCATION	MODULE	NO. MODULES	ELECTRICAL DATA (PER MODULE)			VOLTAGE/ PHASE	COMPRESSOR TYPE/ QTY	NOMINAL COOLING CAPACITY (BTU/h)	NOMINAL HEATING CAPACITY (BTU/h)	COOLING EFFICIENCY EER/EER	HEATING COP @ 47F [or HSPF]	WEIGHT LBS	MODEL NUMBER	NOTES
					MCA	RFS	MFS									
SYSTEM A HP 1A	SYSTEM A HP 1A	3RD ROOF MER	P144	2	53	60	60	208/230V/3 phase 3-wire	INVERTER-DRIVEN SCROLL/2	144,000	160,000	19.3/11.6	3.64	726	PUH-P144TKMU-A	1.2,3,4,5,6,7,8
SYSTEM A HP 1B	SYSTEM A HP 1B	3RD ROOF MER	P120	2	45	50	50	208/230V/3 phase 3-wire	INVERTER-DRIVEN SCROLL/2	120,000	135,000	19.1/12.5	3.75	726	PUH-P120TKMU-A	1.2,3,4,5,6,7,8
SYSTEM A HP 1C	SYSTEM A HP 1C	3RD ROOF MER	P96	2	34	35	40	208/230V/3 phase 3-wire	INVERTER-DRIVEN SCROLL/2	96,000	108,000	19.7/12.6	4.09	532	PUH-P96TKMU-A	1.2,3,4,5,6,7,8
SYSTEM A HP 1D	SYSTEM A HP 1D	3RD ROOF MER	P120	2	45	50	50	208/230V/3 phase 3-wire	INVERTER-DRIVEN SCROLL/2	120,000	135,000	19.1/12.5	3.75	726	PUH-P120TKMU-A	1.2,3,4,5,6,7,8

**(BASED ON MITSUBISHI OR ENGINEER APPROVED EQUAL)**

**NOTES:**

1. NOMINAL COOLING CAPACITIES ARE BASED ON INDOOR COIL EAT OF 80/67°F (DB/MB), OUTDOOR OF 95°F (DB)
2. NOMINAL HEATING CAPACITIES ARE BASED ON INDOOR COIL EAT OF 70°F (DB), OUTDOOR OF 17°F (DB)
3. EFFICIENCY VALUES FOR EER, EER, COP ARE BASED ON AHR 1230 TEST METHOD FOR MIXTURE OF DUCTED AND NON-DUCTED INDOOR UNITS.
4. FOR SYSTEMS WITH MULTIPLE MODULES, REFRIGERANT PIPE DIMENSIONS INDICATE TOTAL SYSTEM COMBINED PIPING DOWN STRAM OF MODULE.
5. MOVED FIELD CHANGE LIST IS IN ADDITION TO FACTORY CHANGE, THIS MUST BE UPHELD BASED UPON FINAL AS-BUILT PIPING LAYOUT.
6. REFRIGERANT PIPING SHALL BE SCHEDULED WIND BRIFLES FOR 100% LOW AMBIENT COOLING DOWN TO WINDS (-) 10°F.
7. DESIGN COOLING OUT DOOR TEMP: 87°F
8. DESIGN HEATING OUT DOOR TEMP: 12°F

**CONDENSATE PUMP SCHEDULE (BASED ON LITTLE GIANI OR ENGINEER APPROVED EQUAL)**

UNIT NO.	SERVICE	WATER PUMP DATA				REMARKS
		GPH	FLHD	SUC. TEMP. °F	H.P.	
GP-1	FAN COIL UNITS	115	20	45	1/12	115V/1 3-48S 1.2


**NOTES:**

1. FURNISHED WITH 6 FT POWER CORD, THERMAL OVERLOAD PROTECTOR, POLYETHYLENE SCREEN.
2. INTEGRAL FLOAT SWITCH, COPPER CHECK VALVE FOR 1" OP COPPER TUBING.

Rev.	Description	Date
	ISSUED FOR CLIENT APPROVAL	09/03/14
	ISSUED FOR BID	11/10/14

**Collado**  
ENGINEERS

2 Holland Avenue  
White Plains, NY 10603  
(914) 332-7658



WARNING: IT IS A VIOLATION OF THE NYS EDUCATION LAW ARTICLE 145 FOR ANY PERSON, UNLESS HE IS ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS ITEM IN ANY WAY.

Client or Agent  
**State University of New York College at Purchase**  
Purchase, New York

Project Title  
SUNY PURCHASE DIMMER ROOMS

Drawing Title  
**MECHANICAL SCHEDULES**

Scale AS NOTED  
Date 7/30/2014  
Drawing No. M-400.00  
Checked C.E. Job No.

Copyright © 2013 by Collado Engineering, P.C.