

DOOR SCHEDULE

BUILDING	DOOR NO.	DOOR TYPE	DOOR MATERIAL	WIDTH	HEIGHT	THICKNESS	FINISH	FRAME MATERIAL	HARDWARE TYPE	FIRE RATING
ENTRY MAILROOM	01	D	ALUM. / GLASS	6'-0"	7'-0"	1 3/4"	PT - _	ALUM.	1	90 MIN
RECEIVING	02	A	H.M.	3'-0"	7'-0"	1 3/4"	PT - _	H.M.	2	NONE
WARE HOUSE	03	A2	H.M.	3'-0"	7'-0"	1 3/4"	PT - _	H.M.	3	90 MIN
SINGLE DOOR OFFICE	02A	A1	H.M.	3'-0"	7'-0"	1 3/4"	PT - _	H.M.	4	NONE
CLOSET	06	3	WOOD	4'-0"	7'-0"	1 3/4"	PT - _	W.D.	5	NONE
STORAGE ROOM	02B	A	H.M.	3'-0"	7'-0"	1 3/4"	PT - _	H.M.	6	NONE
WAREHOUSE	04	C	H.M.	6'-0"	7'-0"	1 3/4"	PT - _	H.M.	7	NONE
ROLL UP DOOR WAREHOUSE		2	GALV. STL.	8'-8"	8'-6"	7/8"	PT - _	GALV. STL.	8	90 MIN
SINGLE DOOR CORRIDOR	05	A2	H.M.	3'-0"	7'-0"	1 3/4"	PT - _	H.M.	9	90 MIN
ROLL-UP EXTERIOR DOOR	06	E-1	GALV. STL.	7'-0"	8'-6"	7/8"	PT - _	GALV. STL.	10	90 MIN
CORRIDOR			GALV. STL.	3'-6"	7'-0"	1 3/4"	PT - _	GALV. STL.	10	90 MIN

PURCHASE

COLLEGE

STATE UNIVERSITY OF NEW YORK

735 ANDERSON HILL RD.
PURCHASE, NY 10577-1400

Project Name: Mailroom / Receiving Area Renovation Project

Project Number: #SU-120814

Location: Plaza Lower Level - Proposed Mailroom / Post Office / Receiving Area

Scale: NTS

Date: 01/12/15

File Path: Z:\I-Projects\Mailroom-Receiving Renovation\Drawings\Door Details.dwg

Mailroom-Receiving

Door Schedule

CSK-034